

SECTION 025803
TRAFFIC SIGNAL ADJUSTMENTS

1. DESCRIPTION

This specification shall govern all work for Traffic Signal Adjustments required to complete the project.

2. MATERIALS

All equipment and materials for adjustments shall be provided by the Contractor, unless indicated otherwise on the drawings.

3. METHODS

The existing signal controls shall be maintained by the Contractor.

Transferring control of the adjusted signal control shall be done by the Contractor.

A minimum of 72 hours advance notice shall be provided to the City Traffic Engineer by the Contractor, prior to transferring control of the adjusted signal control or any other interim signal adjustments necessary to control traffic, unless otherwise noted on the drawings.

Manual traffic direction by the City Police Department shall be arranged and provided for by the Contractor at any signalized intersection at any time that signal control must be interrupted. The Contractor shall arrange for a representative from the City's Traffic Signals Division to be on site to inspect the process of signal control transfer, during the work.

4. MEASUREMENT AND PAYMENT

Unless otherwise specified on the Bid Form, traffic signal adjustments will not be measured for pay, but shall be considered subsidiary to other work.